

INSTALLATION CHECKLIST



This checklist is intended to assist you in preparing and completing the installation of your playground equipment. Unless you contract Luckydog Recreation for your installation, these items are not included in your quote.

- DIG LINE/BLUE STAKE:** Locate underground utilities, sprinkler systems, etc.
- OFFLOADING:** We will provide you with pallet weight, size, and additional offloading instructions.
- INVENTORY:** Make sure your order is correct before signing for shipment, note discrepancies at this time.
- STORAGE:** Owner is responsible for storing equipment. Store in a secure place free from harsh weather.
- SITE PREPARATIONS:** Execute excavation, borders, ADA ramp
- SITE DRAINAGE:** Manufacturer warranties may not be valid unless equipment is properly installed.
- SAFETY SURFACING:** Manufacturer warranties may not be valid unless equipment is properly installed.

NOTE: Manufacturer warranties may not be valid unless the equipment is properly installed.

Our goal is to assist you in any way that we can to make your playground installation safe and easy. If you have any questions regarding the installation of your equipment, please do not hesitate to contact us.

If you wish to contract LDR to do your installation, those services would include concrete footings, erecting vertical poles, assembling other equipment, tightening all hardware, installing weed barrier and safety surfacing, thoroughly inspecting installation upon completion, and providing a comprehensive final walk through with the owner.

INTERMOUNTAIN WEST'S PREFERRED CONTRACTOR
LICENSED - INSURED - CERTIFIED

UPDATED MARCH 2024